

Massachusetts School Building Authority

Deborah B. Goldberg, State Treasurer and Receiver-General

James MacDonald

Chief Executive Officer

Chairperson

John K. McCarthy

Executive Director



MSBA Contractor Roundtable

Occupied School Construction



MSBA Roundtable Discussion

Occupied School Construction



W.T. RICH COMPANY, INC.

Clark Avenue Middle School
Chelsea, MA



Pine Grove Elementary School
Rowley, MA



Manchester Memorial
Elementary School
Manchester, MA



Projects of Focus






Clark Avenue Middle School

- New construction on existing/occupied site
- Total SF: 115,236
 - Phase 1: 77,021 / Phase 2: 38,215
- Budget: \$46,046,367
- MSBA Funded

Overall Challenges

Clark Avenue Middle School

- New 115,236 SF School – Located on Existing School Building Site
- Two Existing Buildings Occupied 90% of Site
 - ❖ 1908 Building = Vacant (52,000 SF)
 - ❖ 1926 Building = Clark Middle School (103,500 SF)



The Prep Work

- The “Big 3”
 - ❖ Maintain an existing campus and keep it safe
 - ❖ Manage the schedule and phases
 - ❖ Manage the schedule towards the client's budget



Key Strategies

Constant and consistent communication

Managing the budget to the schedule

Utilization of February and April vacation

- Open gym floor
- Investigate existing conditions
- Develop scopes
 - Temp boiler
 - Excavation
 - Concrete
 - Shoring

Managing the design to the schedule



Phase 1 Challenges

- Maintain daily safe operation of existing 1926 school building
- Phase 1 demo of existing 1908 building
- Abate 1908 building during the summer
- Relocate and/or cut/cap street utilities and Interior infrastructure
- Setup and maintain temp boiler on the exterior
- Evaluation of exterior egress and supports
- Converting interior walls to exterior weather resistant wall systems
- Phase 1 life safety systems required updating
- Construction of Phase 1 was within 10' of the existing building
- 18 month construction period for 77,021 SF of Phase 1



Existing Conditions May 23, 2015




W.T. RICH COMPANY, INC.

Initial Site Setup May 2015



W.T. RICH COMPANY, INC.

Initial Site Setup May 2015



Perimeter construction fence

School access/egress maintained


Pedestrian sidewalks & crosswalks

Community information board

Construction parking (TBC)



Temp/Relocated Services June 2015



Temporary Utility and MEP Work

Tudor Street

- Cut, cap, relocate:
 - Water Service
 - FP Service
- Gas line: Re-route to temp boiler
- Sanitary: Maintain and protect

MEP Systems


- IT/Data
- AV/PA/Security
- Fire Alarm
- MEP "separation"

Utility Legend

Gas	
Sanitary	
Water	




Phase 1 Demolition July 2015



Temporary Boiler



Phase 1 Foundations November 2015




W.T. RICH COMPANY, INC.

Foundations



W.T. RICH COMPANY, INC.

Phase 1 Steel February 2016



W.T. RICH COMPANY, INC.



Construction of Phase 1 within 10 Feet of the Existing Building

Phase 1 Shell
May 2016



W.T. RICH COMPANY, INC.

Construction Phase 1



W.T. RICH COMPANY, INC.

Phase 2 Challenges

- Maintain daily operation of new school
- Proximity of residents required earth shoring systems and specialty “blind waterproofing” systems at foundations at gymnasium
- Deep excavations for gym required strategic thinking and planning
- Phase 2 to Phase 1 “Tie-Ins” from steel to MEP systems were challenging and complex
- Phase 2 landscaping and site logistics during “summer only” was a logistical challenge




Phase 2 Initial Setup February 2017



W.T. RICH COMPANY, INC.

Phase 2 Initial Setup February 2017



Perimeter construction fence relocated

TWO School access/egress paths


Pedestrian sidewalk & crosswalks

Community information board

Construction parking (TBC)




Phase 2 Demolition April 2017



W.T. RICH COMPANY, INC.




Phase 2 Foundations July 2017




W.T. RICH COMPANY, INC.

Phase 2 Steel September 2017



W.T. RICH COMPANY, INC.




W.T. RICH COMPANY, INC.

Brightview

J Derenzo

Marguerite



PLANTING	PLANTING PLAN	QUANTITY	SCALE
P.1	DECIDUOUS TREES	1/1.5.1	
P.2	EVERGREEN TREES	7/1.5.1	
P.3	ORNAMENTAL TREES	1/1.5.1	
P.4	SHRUBS	3/1.5.1	
P.5	"MOSS" AT RECLAIMED STONE PAVING	7/1.5.1	
A.5	GROUNDCOVER	4/1.5.1	

- NOTES**
PLANTING PLAN
1. FOR SITE LAYOUT SEE DRAWING L-3.1 FOR EXISTING AND PROPOSED GRADE INFORMATION SEE DRAWING L-2.1
 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLETING WORK CALLED FOR ON THE DRAWINGS AND IN THE SPECIFICATIONS WHETHER OR NOT EACH WORK ELEMENT IS NOTED IN THE LEGEND.
 3. STORAGE AREAS FOR CONTRACTOR'S EQUIPMENT AND MATERIALS SHALL BE ON AND WITHIN LIMITS OF WORK AS SHOWN ON THE PLANS AND AS APPROVED BY THE LANDSCAPE ARCHITECT.
 4. CONTRACTOR SHALL VERIFY CONDITIONS IN THE FIELD AND REPORT ANY DISCREPANCIES THAT WILL AFFECT THE INSTALLATION OF PLANTING OR SITE IMPROVEMENTS TO THE LANDSCAPE ARCHITECT.
 5. ALL PLANT MATERIAL SHALL CONFORM TO THE MINIMUM GUIDELINES ESTABLISHED BY THE AMERICAN STANDARD FOR NURSERY STOCK PUBLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMEN, INC.
 6. ALL PLANTS TO BE BALLED AND BURLAPPED UNLESS OTHERWISE NOTED ON PLAN LIST.
 7. THE CONTRACTOR SHALL SUPPLY ALL PLANT MATERIAL IN QUANTITIES SUFFICIENT TO COMPLETE THE PLANTING SHOWN ON THE DRAWING.
 8. ALL PLANTS SHALL BE TAGGED AND APPROVED BY THE LANDSCAPE ARCHITECT AT THE NURSERY PRIOR TO DIGGING OR DELIVERY TO THE SITE UNLESS OTHERWISE DIRECTED BY THE LANDSCAPE ARCHITECT.
 9. CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITY LINES PRIOR TO PLANTING AND SHALL REPORT ANY CONFLICTS TO THE LANDSCAPE ARCHITECT.
 10. STAKE LOCATION OF ALL PROPOSED PLANTING FOR APPROVAL BY THE LANDSCAPE ARCHITECT PRIOR TO THE COMMENCEMENT OF PLANTING.
 11. NO TREES SHALL BE PLANTED BEFORE ACCEPTANCE OF FINISH GRADE AS THEY BORE TO PREVIOUS GRADE.
 12. ALL LANDSCAPED AREAS DISTURBED BY CONSTRUCTION OPERATIONS INSIDE AND OUTSIDE THE LIMIT OF WORK SHALL BE REPAIRED AS SPECIFIED AND AT NO EXTRA COST TO THE OWNER.
 13. ONE OR TWO DAYS BEFORE THE ARRIVAL OF THE PLANT MATERIAL, CONTRACTOR SHALL HARROW OR LOOSEN THE PLANTING SOIL MIX THOROUGHLY.

Layout electrical conduits once stockpile is removed and sub grade is established.
 -Grading - 5/18 - 5/23 (Derenzo)
 -Conduits - 5/24 - 5/30 (Y.E.S.)
 Waterproofing inside 11-line start 5/28 (Chapman)
 Install geofilm 5/31 - 6/4
 *Partial scope by Derenzo
 PRECAST deliveries June 11-June 29th

Area 2 - Grade & Pour Staircase

Move Retaining Wall to correct location 5/29-5/31

Precast Curb to be installed 5/29-6/1

Remainder of Precast Wall 5/29-5/31



KEYPLAN

HMFH Architects, Inc.
 1000 Main Street
 Cambridge, MA 02142
 Tel: 617.878.2770
 www.hmfh.com
 master planning

C S I S
 LANDSCAPE ARCHITECTURE | PLANNING | URBAN DESIGN

BID SET
 07.21.2015

SCHOOL



CLARK AVENUE SCHOOL

KNOWLEDGE / CHARACTER GREAT



W.T. RICH COMPANY, INC.



CLARK AVENUE SCHOOL

WISDOM IS MORE

BOOK ROOM



W.T. RICH COMPANY, INC.



CLARK
AVENUE
SCHOOL



Pine Grove Elementary School

- Gut/Renovation
- Total SF: 87,600
- Budget: \$30,000,000
- MSBA Funded




Phase 1 Challenges

To be completed over **summer of 2018**

- Complete administration area
- Replace existing switch gear, transformer, primary and secondary power lines
- Phase in new FA and SMS
- Have new AHU's and boilers on line for beginning of school year
- Maintain existing school MEP/FP systems in other phases
- Latent site conditions





**Admin Offices, Multi-purpose,
Lobby, Nurse**
Duration: 10 weeks
Area: 18,820 SF

- Full renovation
- Install temporary cafeteria

- New mechanical room and main electrical room
- MEP infrastructure in corridors
- Summer "must" areas (Admin, Multi-purpose, Lobby, Kitchen)
- Temporary classrooms in gymnasium
- Double shift throughout

Key Strategy

- Preconstruction survey to include structural and electrical systems

Phase 1 Summer 2018

Entrance / Lobby



Key Strategy

- ERP for storefront/curtainwall/window trade bids



Glulam Remediation

Key Strategy

- Quick and decisive remediation process
- Coordination with the school to adjust for impacts to food services and assemblies
- Managing expectations



Boiler Room / HVAC Equipment



Key Strategy

- Pre-purchase all equipment through ERP



Electrical Infrastructure

Key Strategies

- Accelerate primary and secondary work through coordination with school and town
- Pre-purchase switch gear through ERP



Phase 2 thru 4 Challenges



All work to be completed while school was occupied



Proposed work was required to be tied into existing work (e.g.- plumbing)




Install and function of AHU's required



Key Strategy

- Close coordination in consultation with school staff and AHJ to develop the plan



Integrating MEP/FP Systems onto Multiple Floors

Key Strategies

- Key Strategies – tying in new services into existing infrastructure
- Working shifts strategically to limit impact to school and its services
- Maintaining existing services until new services are online



Phase 5 Challenges – Most Challenging Phase



Per phase, greatest SF requiring renovation



Bulk of site work and landscaping



Additional site work imposed by the AHJ pressed schedule further



Additional AHU install / full building mechanical balancing



Mold



Mold Remediation

Key Strategies

- Work out of sequence and coordinate with subs accordingly to take advantage of open spaces
- Work closely with design team to expedite remediation and reconstruction methods



Work Volume

Key Strategies

- Required multiple shifts and extended work weeks for all trades
- Requirement incorporated into contract specifications



Last Minute Work by AHJ's

Key Strategy

- Managing expectations with the owner regarding completion and sequencing and prioritizing






PINE
GROVE
SCHOOL









Manchester Memorial Elementary School

- New Construction on Existing Occupied Site
- Total SF: 77,000
- Budget: \$41,000,000
- MSBA Funded
- Budget Pressure (District override required)



W.T. RICH COMPANY, INC.

Challenges

- Extremely tight site
- Phased construction
- Challenging topography
- Wetlands / flood plain
- Access constraints
- Very close proximity to new school
- Neighborhood constraints
- Poor soil conditions / unsuitable soft clay
- Very aggressive schedule
 - ❖ Phase 1 – 39,000 SF classroom addition (11 mos)
 - ❖ Phase 2 – 38,000 SF new east wing (10 mos)
- Budget – tight every step of the way



MANCHESTER MEMORIAL ELEMENTARY SCHOOL - EXISTING CONDITIONS




W.T. RICH COMPANY, INC.


MANCHESTER MEMORIAL ELEMENTARY SCHOOL PROJECT - OVERVIEW




MANCHESTER MEMORIAL ELEMENTARY SCHOOL PROJECT SITE UTILIZATION PLAN - PHASE I



MANCHESTER MEMORIAL ELEMENTARY SCHOOL PROJECT SITE UTILIZATION PLAN - PHASE II



MANCHESTER MEMORIAL ELEMENTARY SCHOOL PROJECT SITE UTILIZATION PLAN - PHASE III



Site Logistics

- Access
- Laydown / storage



Site Access

1. South via Brooke Street
2. Southeast near Summer Street
3. North Side of the Existing Building


1



2



3



Laydown / Storage


- Restrictive policies for on-site storage
- Utilize tennis court
- Access to fields
- Include restoration costs



Occupancy and Phasing

- Looking and planning ahead
- Specific examples
 - ❖ Safe, code-compliant egress
 - ❖ Construction mitigation
 - ❖ Continuity of services






Temporary Provisions at West Wing North Elevation



Continuity of Services Between New Classroom Wing and Existing Building




Schedule Management


- RFP schedule was very tight (not viable). Proposed a revised approach
- Creative early construction packages
- Procurement / material management urgency
- Orchestration and execution in the field (Lean)



RFP Schedule



W.T. Rich Proposed Schedule (Green)



Creative Early Construction Packages

Early Package 1:
Demo/Abatement/Site
Setup – Typical

1. Storefront/curtain
wall – full scope
furnish and install

Early Package 2:
Concrete/Steel/Site
(typical) plus ground
improvement

2. Elevator – trade
contractor bid

Early Package 3:
More creative ideas

3. HVAC Equipment
procurement

4. Electrical –
Main switchboard
procurement



5. Masonry exterior
brick and CMU
veneer

“Base quantity”
defined by WTR

Final quantities by
Masonry Trade
Contractor

Speed of delivery /
winter shutdowns





Orchestration & Execution in the Field

Benefits of Revised Schedule Approach



MEET ALL SCHOOL
OPENING
REQUIREMENTS



PRESERVE ALL
DESIGN
DURATIONS



ALLEVIATE PHASE 1
LEAD TIME
CHALLENGE



INCREASE PHASE 1
DURATION TO 12
MONTHS



INCREASE PHASE 2
DURATION TO 11.5
MONTHS



PERFORM
ABATEMENT/DEMO
SUMMERS ONLY



MORE ATTRACTIVE
TO BIDDERS =>
COST SAVINGS!

CONS:

- Some premium time (abatement/demo)
- Expedited owner move-in (but achievable)



Questions and Discussion

