

BID RESULTS (CSI FORMAT) - Repair Projects [ON OR AFTER JANUARY 1, 2014]

Information as of:
12/16/2025

The information and data contained in this spreadsheet is based on the MSBA's review of construction cost estimates, contracts and other documentation provided by cities, towns, and regional school districts. This information and data is intended for informational purposes only. The data may have changed based on actual construction bids or contract amendments. The MSBA shall have no responsibility or duty to update any of the information contained in this spreadsheet. Additionally, districts may refer to their district and school names using different titles than what is shown in this report. Please contact the Districts for the most current information. The MSBA hereby disclaims any and all liability and responsibility that may arise in connection with the information contained in this spreadsheet. Projects and data may not be listed in the report if the information is not available at the time of report generation. This spreadsheet may include a preliminary review of scope exclusions but all costs identified are subject to review and audit by the MSBA and may not be eligible for reimbursement by the MSBA.

| Date Board Approved | Jul-13 | | Jan-15 | | Sep-15 | |
|---|--|------------|--------------------------------------|--------------|--|-------------|
| District | Greater Lawrence Regional Voc Tech | | Westborough | | Provincetown | |
| School Name | Gr Lawrence Regional Voc Tech | | Sarah W Gibbons MS | | Provincetown HS | |
| Enrollment | 1,400 | | 550 | | 111 | |
| Project Type | Core Program | | Core Program | | Core Program | |
| Project Scope | Repair | | Repair | | Repair | |
| Designer | Richard D. Kimball Co., Inc. (d/b/a NV5) | | Habeeb & Associates Architects, Inc. | | Raymond Design Associates, Inc. | |
| OPM | The Vertex Companies, LLC | | Turner & Townsend Heery | | Atlantic Construction and Management, Inc. | |
| General Contractor | E. Amanti & Sons, Inc. | | Gilbane Building Company | | E. Amanti & Sons, Inc. | |
| DBB or CMR | DBB | | CMR | | DBB | |
| GC Bids Received or GMP Executed | 05/29/14 | | 06/06/16 | | 02/12/16 | |
| GSF | 360,000 | | 110,000 | | 62,645 | |
| Description | Bid Data | | Bid Data | | Bid Data | |
| | Total Cost | Unit Cost | Total Cost | Unit Cost | Total Cost | Unit Cost |
| General Requirements Subgroup | | | | | | |
| 1 General Requirements | \$503,500 | \$1 | \$4,715,110 | \$43 | \$923,980 | \$15 |
| GMP - Fee | | | \$575,037 | \$5 | | |
| GMP - Insurance | | | \$415,403 | \$4 | | |
| GMP - Contingency | | | \$950,000 | \$9 | | |
| Facilities Construction Subgroup | | | | | | |
| 2 Existing Conditions | \$91,400 | \$0 | \$686,700 | \$6 | \$373,200 | \$6 |
| 3 Concrete | \$116,000 | \$0 | \$236,600 | \$2 | \$82,000 | \$1 |
| 4 Masonry | | | \$121,800 | \$1 | \$128,100 | \$2 |
| 5 Metals | \$56,000 | \$0 | \$189,089 | \$2 | \$249,316 | \$4 |
| 6 Wood, Plastics and Composites | \$8,000 | \$0 | \$625,000 | \$6 | \$56,010 | \$1 |
| 7 Thermal and Moisture Protection | \$26,000 | \$0 | \$2,241,900 | \$20 | \$402,460 | \$6 |
| 8 Openings | | | \$1,391,000 | \$13 | \$31,000 | \$0 |
| 9 Finishes | \$17,000 | \$0 | \$1,696,594 | \$15 | \$284,800 | \$5 |
| 10 Specialties | | | \$339,335 | \$3 | \$14,000 | \$0 |
| 11 Equipment | | | \$481,187 | \$4 | | |
| 12 Furnishings | | | \$399,000 | \$4 | | |
| 13 Special Construction | | | | | | |
| 14 Conveying Systems | | | \$70,000 | \$1 | \$32,180 | \$1 |
| Facilities Services Subgroup | | | | | | |
| 21 Fire Suppression | | | \$364,400 | \$3 | \$49,800 | \$1 |
| 22 Plumbing | \$385,000 | \$1 | \$855,000 | \$8 | \$320,000 | \$5 |
| 23 HVAC | \$1,979,900 | \$5 | \$2,550,000 | \$23 | \$1,724,000 | \$28 |
| 26 Electrical | \$301,200 | \$1 | \$2,024,000 | \$18 | \$361,480 | \$6 |
| 27 Communications | | | | | | |
| 28 Electronic Safety and Security | | | | | | |
| 25 Integrated Automation | | | | | | |
| Site and Infrastructure Subgroup | | | | | | |
| 31 Earthwork | | | \$491,500 | \$4 | \$128,000 | \$2 |
| 32 Exterior Improvements | | | | | \$36,000 | \$1 |
| 33 Utilities | | | | | \$36,000 | \$1 |
| Total Construction Cost | \$3,484,000 | | \$21,418,655 | | \$5,232,326 | |
| \$/GSF | \$10 | | \$195 | | \$84 | |
| CMR Preconstruction Services | | | \$161,400 | | | |
| Total Cost (with Precon. Services) | \$3,484,000 | | \$21,580,055 | | \$5,232,326 | |
| Total Cost - Alternates | | | | | | |
| Total Cost (with Alternates) | \$3,484,000 | | \$21,418,655 | | \$5,232,326 | |
| Building Cost (Div3 thru 28) | \$2,889,100 | \$8 | \$13,584,905 | \$123 | \$3,735,146 | \$60 |
| Mark-up Cost (Section 1) | \$503,500 | \$1 | \$6,655,550 | \$61 | \$923,980 | \$15 |
| GMP Contingency as % of Total Con Cost | | | 4.44% | | | |